



Offshore

List of references

Edited : 14/04/2011

WORKS PERFORMED IN BAHRAIN

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2007	DURRAT AL BAHRIAN Co, Ltd	South of Bahrain	Placement of 395 bridge elements 195 T each and building of 9 bridges interlinking the islands and connecting the mainland.	DEMAG CC 2600, DEMAG CC 1800 and 12 axle Nicolas modular trailer and prime mover tractor.

WORKS PERFORMED IN BELGIUM

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2011	GEOSEA	Thornton Bank - Oostende	Installation of Prepiles for 48 Repower turbines of 6MW each on the Thornton Bank in the North sea	Favelle Favco PC300, TC2800
2008	GEOSEA	Thornton Bank - Oostende - Zeebrugge	Installation of the first 6 turbines (5 MW each) on the Thornton sandbank in the North Sea	SPMT's, LR 1750, LG 1550, CC 2800, TC 1100, AC 200, SMLT
2000	HYDROSOIL	Oostdijkbank	Assembly of Radar Tower - Off Shore	DEMAG TC 2400 and LIEBHERR LR 1250

WORKS PERFORMED IN CAMEROON

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2009	GEOSEA	Limbé	Construction of a jetty	DEMAG CC 2500

WORKS PERFORMED IN CONGO

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2001	ROSETTI	Offshore Congo	Offshore	DEMAG TC 2000

WORKS PERFORMED IN DANMARK

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2001	HYDROSOIL SERVICES	Samsø Windfarm	Lifting monopile foundation + superstructures Windfarm 10 x Bonus 2,3 MW	DEMAG CC 2400 SSL

WORKS PERFORMED IN FRANCE

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2003	HYDROSOIL	Bayonne Biaritz	Crane on pontoon type.	KH300



Offshore

List of references

Edited : 14/04/2011

WORKS PERFORMED IN GERMANY

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2010	HOCHTIEF / GEOSEA	Sassnitz	Installation of testpiles for the Baltic II Offshore wind park	TC2800
2009	GEOSEA	Alpha Ventus - Borkum	Offshore installation of 6 turbines (5 MW each)	LR1800
2009	GEOSEA	Borkum	Pre-piling of OWEC Jackets	CC2500
2008	BARD ENGINEERING GMBH	Wilhelmshaven	Installation of first 5 MW near shore wind turbines	CC 6800; Sennebogen 5500 Starlifter
2004	ENERCON	Emden & Bremerhaven	Near & onshore 2 x E112	DEMAG CC8800

WORKS PERFORMED IN GREAT BRITAIN

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2010	DEME	Walney	Offshore installation of 42x 3,6M Siemens turbines	LR1800
jan/07	SMIT SALVAGE	Lymeby Portland harbour	Salvage and recovering load of " MV Napoli "	DEMAG TC 3200 and SUMITOMO SCX 2500
1998-1999	KVAERNER OIL & GAS	Middlesbrough	Building of 4 Offshore Modules & Equipment FSPO.	DEMAG CC 2400

WORKS PERFORMED IN MEXICO

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2006	GEOSEA	Ensenada Mexico	Offshore installation of mooring posts	CC2000 on Zeebouwer
2005	JORGE PARA	Coatzacoalcos	Coating offshore gas pipes	PPM A600C
2005	JORGE PARA	Coatzacoalcos	Coating offshore gas pipes	Demag TC 650
2005	JORGE PARA	Coatzacoalcos	Coating offshore gas pipes	Krupp KMK 5130
2005	INDUSTRIA NEGROMEX	Tampico	Offshore module construction	Liebherr LTM 1300
2005	INDUSTRIA NEGROMEX	Tampico	Offshore module construction	Demag AC435V
2004	JORGE PARA	Coatzacoalco	Coating offshore gas pipes	Manitowoc 3900 Viccon
2004	JORGE PARA	Coatzacoalco	Coating offshore gas pipes	Liebherr LT1050
2004	JORGE PARA	Coatzacoalco	Coating offshore gas pipes	Demag TC 650
2004	JORGE PARA	Coatzacoalco	Coating offshore gas pipes	P & H 6250 TC
2004	JORGE PARA	Coatzacoalco	Coating offshore gas pipes	Liebherr LT1050



Offshore

List of references

Edited : 14/04/2011

WORKS PERFORMED IN NIGERIA				
DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2005	AMEC	Wallsend Assembly Site	Assembling of topsides oil and gas processing equipment on the Floating production, Storage and Offloading vessel Bonga	2x Liebherr LR 1800

WORKS PERFORMED IN NORWAY				
DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2007	STATOILHYDRO / AKER REINERTSEN AS	North Sea - Krirstin Platform	Special lifting system designed to pull off risers for maintenance onboard the Kristin Platform	Special designed lifting device
Dec.05-Aug06	AKER KVAERNER STORD	Ormen Lange gas terminal/Aker Værner Stord Norway	Weighing, site moves, load out, load in barge ballasting, installation by cranes, Installation by SPMT's, Installation by jacking, Engineering, site supervision. Total number of units 180, ranging from 25 tonnes to 500 tonnes	Cranes: 2 no.off Liebherr LR1750, 2 no.off Demag CC2800, 1 no.off Liebherr LR1550, 1 no.off Demag CC2600. SPMT's: 100 axellines Kamag, 48 axellines Goldhofer. Sarens Ballast pumps, Sarens Transrig weighing cells.
2006	THYSSENKRUPP STAHLBAU	Svinesund	Placement of Svinesund Bridge between Sweden and Norway	LIEBHERR LR1750 SPMT's Sarens Twin Barges, Strand Jacks ballasting and mooring equipment.
2004	AKER STORD	Statoil Karsto	Load in / out + installation modules and columns	LR 1800, SPMT's (> 24 axles), CC 2000 + hydraulic cranes

WORKS PERFORMED IN RUSSIA				
DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2009	STEMAT	Hardinxveld - Dordrecht	Transportation of a pilothouse	2 X 16 axlelines Kamag
2009	LUKOIL	Korchagin field - Caspian Sea	In a first stage: transport of modules from Kaliningrad to Astrachan. In a second stage: working platform to assist in the piling and transport barge for the piles and modules (> 1600t).	Twin barges Wim & Tom
2006	LUKOIL	KALININGRAD	Preassemble of base structure of a Fixed Offshore Ice Resistant Off-loading Terminal.	LIEBHERR LR 1800



Offshore

List of references

Edited : 14/04/2011

WORKS PERFORMED IN THE NETHERLANDS

DATE	CLIENT	SITE	WORK PERFORMED	EQUIPMENT INVOLVED
2009	NEM LEIDEN BV	Rotterdam	The construction of a HRSG power plant; Part of the job was the installation of a stack with total height of 65m and total weight of 200t	2 x 12 axle lines SPMT's; AC700
2007	VESTAS	Ijmuiden	60 x V-90 at 60 m	DEMAG CC2800 LR1280
2004	HYDRO SOIL SERVICES	Egmond aan zee	Offshore Erection of Meteomast	LIEBHERR LR 1400/2
1999	IHC HOLLAND N.V.	Kinderdijk	(Water)transport and lifting of parts of a dredger.	Jacking equipment, hydraulic platform trailers, pontoon and hydraulic cranes.